



Sarojini Naidu College for Women

(Govt. Sponsored)

30 Jessore Road, Kolkata - 700 028

Phone : 2559-2583, 2529-1985

Ref. No. :

Date : 05/06/2024

NIQ NO. – 7 OF 2024

Quotations are invited from qualified vendors having experience in civil and interior works for a project at 2nd floor of PG Building at Sarojini Naidu College for Women.

Interested vendors are requested to submit quotations for undertaking the said project in sealed envelopes and submit it in the dropbox at the main building within ten days of the publication of the notice.

Quotations must be in two parts. The first envelope should be a testimony of the previous work done by the vendor. The second envelope should be the financial bid. Both the envelopes must be sealed and marked as 1. Technical bid and 2. Financial bid respectively and must be put into one large sealed envelope.

The following is the scope of the work. All rates must be provided in per sq ft./ per unit basis.

For any further query please contact Pinaki Saha, Office Staff, Sarojini Naidu College for Women.

1. Civil Work

a. Wall - Supply and fixing 5 inch Thick brick wall & both side 12 to 15mm plaster with sand, cement mortar (1:5 + 1:6) with all other necessary materials including scarpfolding and lifting charges as per site requirement.

b. Plumbing Work - Providing & fixing 3/4 CPVC Pipe fixing with necessary fittings including Sink Cock, Angular Stop Cock, Connector, Plumbing materials as per site requirement.

2. Soundproof UPVC Frosted Glass sliding Folding Partition / Soundproof decorative partition for Seminar cum Classrooms

a. Providing & Fixing UPVC frosted glass sliding folding door for partition wall with 73 mm x 60 mm frame, 104 mm x 60 mm shutter with Saint Gobain or equivalent 5 mm/ 7 mm toughened glass including full G. I reinforcement 1.5 mm plate & EPDM gasket

Equivalent soundproof decorative partition may also be considered

PS – About 90% sound reduction must be ensured

3. False Ceiling Work

a. Providing & Fixing of Armstrong Mineral Fiber Acoustical Suspended Ceiling System or equivalent

b. Providing & Fixing of Armstrong Normal Grid false Ceiling System or equivalent

4. Sound System (PI System)

Providing & fixing of PI system (04 No's sound box with 04 inch speaker with 10 channel amplifier), Addressing microphone with Stand and other PI system for the conference room as per layout design by architect

5. PODIUM

a. Providing & fixing acrylic podium for conference room



Sarojini Naidu College for Women

(Govt. Sponsored)

30 Jessore Road, Kolkata - 700 028

Phone : 2559-2583, 2529-1985

Ref. No. :

Date : 05/06/2024

b. Lectern stands - lectern stand's design including sloped reading surface, ensuring comfortable reading angles for the speaker it comes with a convenient selves or storage space for keeping presentation materials. The podium makes with 08 mm thick acrylic sheet width 55 cm, height 111 cm, depth 54 cm. as per design by architect

6. Desk and Chair for college level students

Desk and Chair for college level students – made of mild steel and ply. Design subject to approval of the concerned authorities.

7. Glass Partition with aluminium channel

a. Aluminium sections making a grid covered with 12 mm MR grade plywood on both sides and finished in 1mm laminate on both sides upto 9' height and finish the balance with Grid false ceiling with paint finish, making necessary provisions for Electrical conduiting, switch boards, in all respects. The framework spacing not exceeding 600mm both ways (horizontal and vertical). The framework shall be secured between floor sill/ Lintel level with 25 x 50mm x 1.2mm thick horizontal Aluminium section. Framework to be secured to Floor / Walls / Columns using 75mm metal screws and dowels as per details. The framework to have 50 x 50 x 1.2mm aluminum 'L' angle fixed to aluminium box section as per detail drawings. specifications. (Upto false ceiling height, skirting bill)

8. Workstation Area

Providing & Fixing of Workstation (05 setter) Area with 19 mm MR grade ply & approved laminate with all hardware materials as per detail design by architect

9. Ply Partition for sitting area

Aluminum sections making a grid covered with 12 mm MR grade plywood on both sides and finished in 1mm laminate on both sides upto 6' height, the framework spacing not exceeding 600mm both ways (horizontal and vertical).

10. Pantry & Overhead Storage area

a. Overhead Storage Unit – Providing & Fixing overhead cabinet for storage in 12mm MR Grade ply, finished in approved laminate including necessary hardware fittings as per drawing by architect.

b. Storage Counter - Platform storage Counter in 19mm MR Grade ply and approved laminate, top finished with granite, all internal surfaces finished with laminate, including necessary hardware for openable door panels, as per detail drawing by architect.

Dr. Swagata Das Mohanta

Principal

Principal
Sarojini Naidu College
for Women
Govt. Sponsored